

Foz Tua

Castanheiro – PT – 2012

Capacity (t)	56 t (2x28)	Travel speed	7 m/s
Vertical hook rise	220 m	Length	440 m
Hoisting speed	2,5 m/s		

With a lifting capacity of 28 metric tons, two radial cable cranes handled key transport and lifting tasks at the construction site.

They ensured a steady supply of concrete to the construction sites while also enabling the safe transport of heavy machinery and equipment. As a result, they made an important contribution to the efficient implementation of the project.